

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 29 NR. 2 W.

Otsego

COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 3-4-9-10.

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

7" Aspen	-	S50E	-	12 links
5" Aspen	-	S53W	-	19½ links
7" Maple	-	N19W	-	71½ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was restored previously from the government Bts by G.F. DeLaMater. Corner was remonumented by Forestry Division Land Surveyor to perpetuate a government corner and to better identify state land boundaries. Could find no iron but found a good stake point relative to the record witnesses.

Corner was placed and witnessed April 27, 1959.

SURVEYORS SEAL

SIGNED Kenneth J. DeLing DATE 4/28/59
REGISTERED LAND SURVEYOR