

SURVEY & REMONUMENTATION

APR 25 1995

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

LIBER 0004 PAGE 18

For corners in
COMMISSION
OTSEGO
(County)

	Located In:	Corner Code #
1. Public Land Survey	T 29N R 2W	K-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD

94 DEC 14 PM 4:02

EVELYN H. PRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James L. Schwandt, in a field survey on November 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Harvey Mellen, 1856
Set Post
10" Sp. Pine N20°W 20 Lks.

G.F. Delamater, 1933
Fd. Houghton's P. & roots of
Gov't B. Set 1/2" x 36" bar
12" B. Oak S40 1/2°E 137.20'
18" Y.P.S. N21°E 126.40'

N. Caldwell, 1967
Fd. 1/2" bar and
G.F. Delamater witnesses

Carl I. Robinson #16390, 1989
Fd. 1/2" iron. Set O.C.M.
7" J. Pine N47°E 21.09'
18" W. Pine S39°E 30.92'
10" J. Pine S40°W 39.90'
7" J. Pine N51°W 46.29'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found O.C.M. set by C.I. Robinson; Liber 3, Page 28, 5-9-89. O.C.M. fits Black Oak witness to Delamater's 1/2" x 36" bar. Delamater had recovered G.L.O. Post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Found O.C.M. is accepted as a careful and faithful perpetuation of the position of the original corner.

7" J. Pine N47°E 20.94' Fd. Nail
18" W. Pine S55°E 30.82' Fd. Nail
10" J. Pine S42°W 39.90' Fd. Nail
7" J. Pine N56°W 46.15' Fd. Nail



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Dec 13 1994 _____
Date Chairman

Signed by James L. Schwandt
James L. Schwandt, PS 26466
Surveyor's Michigan License No. _____

Date December 7, 1994