

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. 29 N. R. 3 W.	A-12; B-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION <u>31</u>	T. 29 N. R. 3 W.	B-12/9
4. LOT NO. _____	RECORDED PLAT _____	
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 8, 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:


B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-12 Set by proportionate measurement between section corners.
- B-12 Set corner at computed intersection of $\frac{1}{4}$ lines.
- B-12/9 Set to mark E-W $\frac{1}{4}$ line on lakeshore.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-12	B-12	B-12/9
DNR mon. & red-top post	2½' of 1¼" pipe	2½' of 1¼" pipe
6" W. Pine N50°E 18.1	20" W. Pine N24°E 30.4	8" Maple N60°E 22.0
10" W. Pine N12°E 52.9	13" W. Pine N56°W 71.3	5" Maple N07°E 29.9
		11" W. Birch S45°W 19.0
		water's edge East 23

SIGNED BY *Kenneth J. Ostling* DATE _____
 SURVEYOR'S MICHIGAN REGISTRATION NO. 10068



FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
 APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ OTSEGO COUNTY