

# SURVEY & REMONUMENTATION

APR 25 1995

For corners in

**OTSEGO**  
**COMMISSION**  
(County)

## OTSEGO COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO ACT 345, PA 1990

LIBER 0004 PAGE 27

Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_

- |                                    |                          |                  |
|------------------------------------|--------------------------|------------------|
| 1. Public Land Survey              | T <u>29N</u> R <u>3W</u> | _____ H-11 _____ |
|                                    | T _____ R _____          | _____            |
|                                    | T _____ R _____          | _____            |
|                                    | T _____ R _____          | _____            |
| 2. Property Controlling in Section | S _____ T _____ R _____  | _____            |
|                                    | S _____ T _____ R _____  | _____            |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____  | _____            |
|                                    | S _____ T _____ R _____  | _____            |

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

94 DEC 14 PM 4:04

EVELYN H. PRATT  
CLERK / REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, James L. Schwandt, in a field survey on November 23, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

G.L.O. Harvey Mellen, 1857  
Set Post  
12" Sugar S32°W 8 Lks.  
9" Beech S50°E 35 Lks.

G.F. Delamater  
Set ½" bar  
Conc. Mon. North 34.0'  
Fence lines North & South

Gerald R. McKelvey #19001  
August 27, 1975  
Left ½" iron as found  
North 34.00' Conc. Mon.  
S40°E 73.87' Tag in U. Pole  
South 33.00' ½" iron rod  
Witnesses intact, checked by  
Larry M. Gerschbacher  
September 9, 1977


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found ½" iron bar in centerline of Marlette Road, McKelvey's utility pole and ½" iron south, as well as Delamater's concrete monument North.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

H-11 Found ½" iron bar and replaced it with O.C.M.  
O.C.M. is accepted as a careful and faithful reestablishment of the position of the original corner.

Conc. Mon. North 34'  
Tag in P.P. S40°E 73.87'  
½" iron bar South 33.00'  
In centerline of Marlette Road



**OTSEGO COUNTY REMONUMENTATION**

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

DEC 13, 1994  
Date

*[Signature]*  
Chairman

Signed by James L. Schwandt  
James L. Schwandt, PS  
Surveyor's Michigan License No. 26466

Date December 7, 1994