

OTSEGO COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE

LIBER 0004 PAGE 68

Filing Requirement of Act 74, Mich. P.A. 1970  
 ALSO ACT 345, PA 1990

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 29N R 3W	K-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 95 NOV -2 AM 10:12  
 EVELYN H. PRATT  
 CLERK/REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, JAMES L. SCHWANDT, in a field survey on NOVEMBER 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Harvey Mellen, 1857  
 Re-established 1/4 corner  
 8" W. Birch S83°W 14'  
 12" W. Pine N62°E 12'

G.F. Delamater, 1946  
 1/2" x 24" bar  
 6" Red Oak S87°W 50.4'  
 6" Red Oak S48°W 67.8'

Wynn Wakenhut  
 August 28, 1969  
 Set 1/2" bar  
 No wit Fd.

Gerald R. McKelvey #19001  
 Fd. 1/2" bar in corner near Wakenhut survey distance location  
 S45°E 9.68' tag in 8" Aspen; N30°E 11.19' tag in 8" R. Oak;  
 West 6.57' tag in 5" Maple

Carl I. Robinson replaced  
 1/2" Iron with O.C.M.  
 LCRC, L. 2, Pg 225  
 Fd Spk in 8" Aspen S45°E, 9.82'  
 Fd Spk in 8" Oak N30°E, 11.19'  
 Fd Spk in 5" Maple West 6.39'  
 Set Spk in 6" Maple S10°W, 19.95

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd O.C.M. which checked all of McKelvey's wit. And Robinson's wit. C. I. Robinson replaced what was probably W. Wakenhut Iron with the O.C.M. This location used by GRM and others in subsequent surveys.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-4 Otsego Co. Mon Fd  
 Fd. Spk in 8" Aspen S45°E, 9.82'  
 Fd. Spk in 8" Oak N30°E, 11.19'  
 Fd. Spk in 5" Maple West 6.39'  
 Fd. Spk in 6" Maple S10°W, 19.95  
 Fd. Spk 8" Maple S78°E, 15.43

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer  
 Group, pursuant to Act 345, PA 1990.  
 Aug 3, 1995  
 Date Chairman



And is accepted as a careful and faithful re-establishment of the position of the original corner.

Signed by James L. Schwandt Date August 3, 1995  
 Surveyor's Michigan License No. 26466