

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Otsego _____ Located In Otsego Lk Twp. Corner Code #
 (County)

1. Public Land Survey	T	<u>29N</u>	R	<u>3W</u>	<u>A-8</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	_____	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on October 1, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

A-8 G.L.O. James H. Mullet 1839
 Set quarter section post
 Wit: Beech 12 S43°W 23 links
 Beech 12 N20°W 22 links

James L. Schwandt P.S. #26466 1987 prorated this corner position while doing a survey in section 19, T.29., R.3W.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A-8 Found 1/2" iron rod with P.S. cap #26466 as set by James L. Schwandt in January of 2001.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-8 Found 1/2" capped iron rod replaced with Otsego County Monument accepted as a careful and faithful re-establishment of the position of the original corner.

Wit: 8" Oak	N40°W	28.62'
10" Oak	N48°E	28.38'
5" Twin Beech	S78°W	31.22'
12" Beech	S45°E	1.40'
N-S Fence	West	56'±
E-W Fence	North	24'±
Carsonite Post	North	1'±



Signed by: Carl T. Kiiskila
 Surveyor's Michigan License No.: 33981

Date: 12-23-02

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													