

OTSEGO COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In:  
Otsego Located In Otsego Lk. Twp. Corner Code #  
 (County)

1. Public Land Survey	T	<u>29 N</u>	R	<u>3 W</u>	<u>A-11</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on May 24, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

A-11 GLO James Mullet, D. S. 1839  
 Set corner sections 25, 36  
 Wit: 12" Beech N81°W 34 links  
 14" Beech S85°W 35 links

Liber 1, Page 417, Kenneth J. Ostling R.L.S. #10068,  
 1974 found a rotted stake point and Hoffman's new bearing  
 trees and set a standard DNR monument with red topped  
 post.

Wit: 12" Twin Beech N22°E 23.0'  
 7" Beech S03°E 1.4'

Book 2, Page 162 Otsego Co. survey notes ( Nov. 1919 )  
 Hoffman found post and one bearing tree stump added new  
 witnesses.

Wit. Pine 4" N47°W 55 links  
 Beech 12" S43°W 58 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

A-11 Found a standard DNR monument bent from road  
 grading. Replaced bent monument with a new DNR  
 monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-11 Set standard DNR monument and carsonite post is  
 accepted as a careful and faithful perpetuation of the  
 position of the original corner.

Wit: 14" Twin Beech N22°E 23.06'  
 14" Maple S78°E 33.16'  
 14" Twin Maple S30°E 23.35'  
 9" Beech S03°E 1.75'  
 16" Maple S86°W 32.91'  
 Centerline trail road West 15' ±



Signed by:

Carl T. Kiiskila

Date:

12-23-02

Surveyor's Michigan License No.:

33981