

# SURVEY & REMONUMENTATION

APR 25 1995

## COMMISSION

OTSEGO COUNTY REMONUMENTATION

### LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO ACT 345, PA 1990

BOOK 0004 PAGE 038

OTSEGO (County)	Located In:	Corner Code #/
1. Public Land Survey	T 29N R 4W	C-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
34 DEC 29 PM 1:30  
EVELYN H. PRATT  
CLERK/REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, James L. Schwandt, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Harvey Mellen, 1856  
Set Post  
12" Y. Birch N75°E 15 Lks.  
9" Beech N25°W 29 Lks.

G.F. Delamater, 1949  
Set 1/2" x 48" bar  
40" W.P.S. N88°E 36.2'  
30" W.P.S. S42°W 32.2'  
Set by measurement

Stanley O. Thorson #5788, 3/6/66  
Fd. 1/2" bar and  
Delamater witnesses

Carl I. Robinson #16390, June 21, 1988 - Fd. 1/2" bar and W.P.S. N88°E 32.2' w/Delamater Tag, Set O.C.M.  
7" Maple N83°E 44.24', 40" W.P.S. N88°E 36.2', 8" Beech South 14.02', 8" Beech S7°W 12.41', 4" Maple S58°W 9.88'


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found O.C.M. set by C.I. Robinson per L.C.R.C. L3, P8, and both Delamater W.P.S.'s cited by S Thorson in C.S.R. of 1956, L3, P 348.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-4 Found O.C.M. and is accepted as a careful and faithful reestablishment of the position of the original corner.

4" Maple S58°W 9.88' Found Spike  
7" Twin Maple N83°E 44.24' Found Spike  
W.P.S. N88°E 36.2'  
8" Beech South 14.02' Found Spike



OTSEGO COUNTY REMONUMENTATION  
Approved by the County Survey Peer  
Group, pursuant to Act 345, PA 1990  
Date Dec 22, 1994 Chairman [Signature]

Signed by [Signature]  
James L. Schwandt, PS  
Surveyor's Michigan License No. 26466

December 7, 1994