

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION
For corners in

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

1994 PAGE 040

OTSEGO COUNTY MICHIGAN
RECEIVED FOR RECORD
94 DEC 29 PM 1:30
EVELYN L. PRATT
CLERK / REGISTER OF DEEDS

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 29N R 4W	C-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James L. Schwandt, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Harvey Mellen, 1856
Set Post
10" Maple S58°W 4 Lks.
7" Beech N5°E 4 Lks.

Carl I. Robinson #16390, 1980
Fd. T/iron w/RLS Cap #6525
Fd. Spk. 14" R. Pine N25°W 41.87'
Fd. Spk. 6" R. Pine S65°E 28.56'
Fd. Spk. 6" R. Pine S60°W 12.00'
Fd. Spk. in Tag #6525, 30" Stump S220°E 10.98'
Replaced corner w/O.C.M.

T.F. Schweigert #6525, 1955
Set T/iron midway on line per survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found O.C.M. set by C.I. Robinson per L.C.R.C. L2, P168, and per Robinson survey dated 2/6/80. This survey notes: "Used W. line of Section 29 per survey by T.F. Schweigert, RLS #6525 dated 1/18/55," and this line fits G.L.O. to an acceptable degree.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:


C-10 Found O.C.M. is accepted as a careful and faithful reestablishment of the position of the original corner.

6" R. Pine S65°E 28.56' Found Spike
30" P.S. S20°E 10.98' Found "T" Iron w/Tag # 6525
20" P.S. S86 °W 48.82' Found Tag # 6525
14" R. Pine N25°W 41.87' Found Spike

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
Dec. 22, 1994 Date [Signature] Chairman

Signed by James L. Schwandt
James L. Schwandt, PS
Surveyor's Michigan License No. 26466



December 7, 1994