

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 0004 PAGE 69

For corners in <u>Otsego</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>4W</u>	<u>D-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 NOV -2 AM 10:12
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS
 Register of Deeds Stamp & File Number

I, James L. Schwandt, in a field survey on December 5, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1					
3											
4	7	6	5	4	3	2	1				
5											
6	16	17	18	19	20	21	22	23	24	25	26
7											
8	19	20	21	22	23	24	25	26	27	28	29
9											
10	30	29	28	27	26	25	24	23	22	21	20
11											
12	31	32	33	34	35	36	37	38	39	40	41
13											

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Harvey Mellen, 1856
 Set Post
 20" Sugar S35°W 26 lks
 20" Hemlock N13°W 84 lks

Corner recorded by
 S. Thorson #5788, Mar 1958
 Corner submitted for recording by
 T. F. Schweigert, R.S. #6525,
 Jan. 1955
 1/2" Bar, 24" Set MPOL
 24" White Pine, S32°E, 10.8'
 20" White Pine, S81°W, 45.5'

Replaced Schweigert's T-Bar with O.C.M.
 Carl I. Robinson, 1980
 Spk. P.P. N80°W 88'
 Spk 8" Maple S55°W 30.23'
 Spk 8" Maple S40°E 37.36'
 Spk 6" & 10" Tw. Maple N40°E 31.72'
 Corner is 52°E of centerline of N-S Road

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fd O.C.M. set by C. I. Robinson in 1980. Robinson replaced Schweigert's T-Bar with the O.C.M. C. I. Robinson wit. From LCRC, L-2, Pg 168 were all found.

DEC 11 1995
 COMMISSION


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-9 Found O.C.M. is accepted as a careful and faithful re-establishment of the position of the original corner.

6"-10" Twin Maple N57°E 31.72' Found Spike
 8" Maple S40°E 37.36' Found Spike
 8" Maple S55°W 30.23' Found Spike
 Power Pole N80°W 0.88' Found Spike

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Pear
 Group, pursuant to Act 345, PA 1990.
 Date Aug 3 1995 Chairman [Signature]



Signed by James L. Schwandt
 Surveyor Michigan License No. 26466

Date 8-3-95