

REMONUMENTATION

APR 25 1995

OTSEGO COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO ACT 345, PA 1990

LIBER 0004 PAGE 41

For corners in

OTSEGO <small>(County)</small>	Located In:	Corner Code #/
1. Public Land Survey	T 29N R 4W	D-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY,
 MICHIGAN
 RECEIVED IN RECORD
 94 DEC 29 PM 1:31
 EVELYN H. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, James L. Schwandt, in a field survey on December 5, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Carl I. Robinson #16390, 1980 Fd. T/iron w/RLS Cap #6525, Replaced w/O.C.M. Set Spk. Clump 5"-10" Maples S75°W 13.51' Set Spk. 12" Tw. Maple S45°W 24.46' Set Spk. 8" Tw. Maple N72°E 36.62' Set Spk. 12" Maple S35°W 47.44'	T.F. Schweigert #6525, 1955 set T/iron at intersection of 1/4 lines
---	---

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found O.C.M. set by C.I. Robinson 6/23/80 replacing T-Iron & cap #6525 per survey by T.F. Schweigert dated 1/18/55, and listed on L.C.R.C. L2, P168.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

D-10 Found O.C.M. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner:

8" Twin Maple N72°E 36.62' Found Spike
 12" Maple S35°W 47.44' Found Spike
 12" Twin Maple S45°W 24.46' Found Spike
 Clump of 5"-10" Maples S75°W 13.51' Found Spike



OTSEGO COUNTY REMONUMENTATION
 Approved by the County Survey Pe
 Group, pursuant to Act 345, PA 199
 Dec 12, 1994
 Date Chairman

Signed by James L. Schwandt
 James L. Schwandt, PS 26466
 Surveyor's Michigan License No. _____