

REMONUMENTATION

APR 25 1995

COMMISSION
For corners in

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

LIBER 0004 PAGE 44

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 29 PM 1:31
LYLE H. PRATT
CLERK / REGISTER OF DEEDS

OTSEGO (County)	Located In:	Corner Code ##
1. Public Land Survey	T 29N R 4W	H-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, James L. Schwandt, in a field survey on December 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. Harvey Mellen, 1856
Set Post
8" Beech N10°W 21 Lks.
16" Beech S26°W 20 Lks.

G.F. Delamater, 1949
Set 1/2" x 48" bar, Fd. stumps
of both Gov't B's & two P's,
15.4' West and 12.6' South of
Temp. 4" Elm S77°E 24.3'
6" Ironwood S17°E 14.6'

George E. Young, 1972
Fd. sq. post, replaced with
T/iron, 11" H. Maple S20°E 4.7'
6" Basswood S45°W 18.7'
4" H. Maple N57°W 34.5'

Gerald R. McKelvey #19001, 1977
Fd. T/iron, Fd. all of George Young's
witnesses

George J. Avendt, Jr. #16034
Fd. T/iron & witnesses of record
Set O.C.M., Set Spk
6" Maple N37°E 18.32'

James L. Schwandt #26466
Jan. 2, 1986
Fd. T/iron & witnesses of record


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found O.C.M. set by G.J. Avendt L2, P 285 fitting Young's witnesses and Delamater's Elm and Ironwood. Delamater's position based on recovered G.L.O. evidence.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 Found O.C.M. is accepted as a careful and faithful perpetuation of the position of the original corner.

11" Maple S20°E 4.7' Found Tag
6" Ironwood S17°E 14.6' Found Spike
6" Basswood S45°W 18.7' Found Tag
4" H. Maple N57°W 34.5' Found Tag



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer
Group, pursuant to Act 345, PA 1990.
Dec. 22, 1994
Date

[Signature]
Chairman

December 7, 1994

Signed by *[Signature]*
James L. Schwandt, PS 26466
Surveyor's Michigan License No. _____