

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Otsego (County)	Located In	Corner Code #
1. Public Land Survey	T <u>29N</u> R <u>4W</u>	<u>B-10</u>
2. Property Controlling in Section	S <u>30</u> T <u>29N</u> R <u>4W</u>	<u>5</u>
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on April 8, 2003 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-10 This corner position was not established during the original government survey.

5- This corner position was not established during the original government survey.

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

B-10 Established the center of section 30 at the intersection of the North-South and East-West one-quarter lines.

5- Established the Northwest corner of the Southwest quarter of the Northeast quarter of section 30 as per B.L.M. instructions for the subdivision of a section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-10 Set standard DNR monument.

Wit: 5" Cherry	S42°W	13.60'
7" Cherry Clump	N34°W	20.50'
6" J. Pine	N51°E	15.66'
5" J. Pine	S51°E	22.75'
Carsonite Post	North	1'±

5- Set 5/8" X 32" capped iron rod P.S. #33981

Wit: 12" Cherry	N53°W	79.76'
4" Twin R. Pine	S78°W	20.66'
4" R. Pine	S45°E	22.47'
7" Cherry	N80°E	55.36'
Carsonite Post	North	1'±

Signed by:

Carl T. Kiiskila

Date:

11-18-03

Surveyor's Michigan License No.:

33981

