

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Otsego _____ Located In Hayes Twp. Corner Code #
 (County)

1. Public Land Survey	T	29N	R	4W	K-8
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	T	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	T	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on October 31, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

K-8 G.L.O. Harvey Mellen D.S. 1856.
 Set quarter section post
 Wit: W. Pine 24" South 11 links
 Hemlock 14" N04°W 23 links

Liber 1, Page 375, 1974 Gerald McKelvey R.L.S. #19001
 found a conservation monument.
 Wit: S75°E 35.20' "NBT" blaze on stump
 N40°W 16.40' "NBT" blaze on stump
 West 22.20' "NBT" blaze on stump

1932 G.F. DeLaMater set 1/2" bar from original B.T. stumps
 Wit: 16" W. Pine stump S88°W 33 1/2" links

August 1959 Kenneth J. Ostling R.L.S. #10068 found 1/2" iron
 bar previously established by G.F. DeLaMater in 1932.
 Set 1" pipe with 4" brass cap.
 Wit: 15" W. Pine stump S88°W 33 1/2" links (22.1')

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-8 Found a 1" pipe with 4" Brass cap as set by
 Kenneth J. Ostling.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8 Department of Conservation monument accepted as a
 careful and faithful perpetuation of the position of the original
 corner.

Wit: 5" Spruce	S87°W	28.98'
6" Twin Maple	S37°W	44.25'
8" Twin Red Pine	N50°E	34.20'
4" Cherry	East	39.72'
16" W. Pine stump	N85°W	22.35'
Carsonite Post	North	1±



Signed by:

Carl T. Kiiskila

Date:

12 - 23 - 02

Surveyor's Michigan License No.:

33981