

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Otsego _____ Located In Hayes Twp. Corner Code #
 (County) _____

1. Public Land Survey	T	<u>29N</u>	R	<u>4W</u>	<u>K-11</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	T	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	T	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on October 31, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4			3			2
3													
4	7			8			9			10			12
5													
6	18			17			16			15			14
7													
8	19			20			21			22			24
9													
10	30			29			28			27			26
11													
12	31			32			33			34			36
13													

A. Description of original monument and accessories and/or subsequent restoration:

K-11 G.L.O. Harvey Mellen D.S. 1856
 Set post corner of sections 25,26,35, and 36
 Wit: Hemlock 18" N14°E 21 links
 Y. Pine 14" S34°W 53 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

K-11 Found 1/2" rod fitting swamp ties to the West and GLO distance south reasonably well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-11 Set Otsego County Monument is accepted as the best available evidence of the position of the original corner.

*15" White Pine	N71°E	24.91'
6" White Pine	N11°W	10.12'
*12" White Pine	S86°W	17.71'
*15" White Pine	S19°W	28.73'

*Old witness by others

Signed by:

Carl T. Kiiskila

Date:

12-23-02

Surveyor's Michigan License No.:

33981

