

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. PA 1970

For Corners In:
 Otsego _____ Located In Hayes Twp. Corner Code #
 (County)

1. Public Land Survey	T	<u>29 N</u>	R	<u>4 W</u>	<u>M-11</u>
	T	_____	R	_____	_____
2. Property Controlling in Section	S	T	R	_____	_____
	S	_____	R	_____	_____
3. Miscellaneous Property in Section	S	T	R	_____	_____
	S	_____	R	_____	_____

4. Lot No: _____ Recorded Plat: _____

5. Private Claims: _____

I, Carl T. Kiiskila, in a field survey on May 24, 2002 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

M-11 GLO James Mullet, D. S. 1839
 Set corner sections 25, 36
 Wit: 12" Beech N81°W 34 links
 14" Beech S85°W 35 links

Liber 1, Page 417, Kenneth J. Ostling R.L.S. #10068, 1974 found a rotted stake point and Hoffman's new bearing trees and set a standard DNR monument with red topped post.

Book 2, Page 162 Otsego Co. survey notes (Nov. 1919)
 Hoffman found post and one bearing tree stump added new witnesses.

Wit: 12" Twin Beech N22°E 23.0'
 7" Beech S03°E 1.4'

Wit. Pine 4" N47°W 55 links
 Beech 12" S43°W 58 links

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

M-11 Found a standard DNR monument bent from road grading. Replaced bent monument with a new DNR monument.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-11 Set standard DNR monument and carsonite post is accepted as a careful and faithful perpetuation of the position of the original corner.

Wit: 14" Twin Beech N22°E 23.06'
 14" Maple S78°E 33.16'
 14" Twin Maple S30°E 23.35'
 9" Beech S03°E 1.75'
 16" Maple S86°W 32.91'
 Centerline trail road West 15' ±



Signed by: Carl T. Kiiskila

Date: 12-23-02

Surveyor's Michigan License No.: 33981