

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30. NR. 2. W. . .

----- Otsego -----

COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 34 and 35 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 24" W. Pine stump - N17W - 85 1/2 links

* 36" W. Pine stump - S80E - 46 links

* Old NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was previously restored by Houghton and DeLaMater from government BT stumps which are still in place. Corner was re-monumented and rewitnessed by Forestry Division land surveyor to perpetuate a government corner and identify state land boundary. Falls at NE corner of new pine plantation.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 5/11/59
REGISTERED LAND SURVEYOR