

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>30</u> N. <u>●</u> R. <u>2</u> W. <u>●</u>	K-10; K-11; K-12
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ E. _____ S. _____ R. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on October 28, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-10 No evidence of a previous corner. Set by proportionate measurement between section corners.
  - K-11 No previous corner. Set by single proportionate measurement between 1/4 corner south and section corner north, per original survey procedure. Possible line tree and original 1/4 corner south.
  - K-12 Found 1/2" iron bar and witnesses at corner. Also remains of probable U.S.B.T. Probably by G. F. DeLaMater.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-10	K-11	
Set DNR mon. & red-top post	Set DNR monument	Set DNR mon. & red-top post
4" Maple N20°W 23.1	8" Maple S88°W 37.4	*12" Pine Stump S33°E 33.7
5" Maple S20°W 40.4	8" R. Oak N15°E 49.4	*Pine Stump N72°E 61.5
		3" R. Pine S70°W 75.6
		5" Maple S56°E 42.1
		*old N.B.T.

SIGNED BY *Kenneth J. Ostling* DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

