

MAY 28 1997

COMMISSION

OTSEGO COUNTY REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ALSO ACT 345, PA 1990

<u>Otsego</u> (County)	Located In:	Corner Code #
	N. CHESTER TOWNSHIP	
1. Public Land Survey	T <u>30N</u> R <u>2W</u>	<u>A-4</u>
	T___ R___	_____
	T___ R___	_____
	T___ R___	_____
2. Property Controlling in Section	S___ T___ R___	_____
	S___ T___ R___	_____
3. Miscellaneous Property in Sec.	S___ T___ R___	_____
	S___ T___ R___	_____

OTSEGO COUNTY MICHIGAN
 RECEIVED FOR RECORD
96 DEC 30 PM 2:13
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, **James L. Schwandt**, in a field survey on **Oct. 21, 1996** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4	7		8		9		10		11		12		
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|---|--|
| <p>A-4 T30N-R2W
 G.L.O. James H. Mullet, 1839
 Set Post
 12" Sugar S15°W, 34 Links (22.44')
 12" Sugar N85°W, 32 Links (21.12')</p> <p>CSR (1-37)
 J.W. Sanborn, 1887
 Hemlock 24" N68°E, 33 Links (22.44')
 Sugar 12" N85°W, 32 Links (21.12')
 Hemlock 24" N12°W, 17 Links (11.22')</p> | <p>CSR (2-274)
 G. F. Delameter, 1922
 48" W. Pine Stump N65°E, 99 Links (65.34')
 40" W. Pine Stump S60°W, 55 Links (36.30')
 36" W. Pine Stump N67°W, 98 1/2 Links (65.01')
 Steel Ford Axle @ Corner
 Fnd Both Government B's & P</p> <p>CSR (3-263)
 S. Thorson, 1968
 MSHD Notes, 1966</p> | <p>CSR (3-262)
 Delameter Fnd Axle
 CM West, 34.07'
 CM East, 33.65'
 17" Maple N62°E, 45.40'
 24" Maple Clump S35°E, 66.54'</p> <p>*SEE BACK FOR ADDITIONAL INFORMATION</p> |
|---|---|--|


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


- Fnd OCM ±1' Deep
- Fnd Spk 12" Twin Maple N40°E, 24.00'
- Fnd Old Blaze in 12" Tri. Maple and Set Spk N80°E, 16.63'
- Fnd Old Blaze in 12" Tri. Maple and Set Spk N70°W, 29.10'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- OCM, and is accepted as a careful and faithful perpetuation of the position of the original corner.
- Fnd Spk 12" Twin Maple N40°E, 24.00'
- Fnd Old Blaze in 12" Tri. Maple and Set Spk N80°E, 16.63'
- Fnd Old Blaze in 12" Tri. Maple and Set Spk N70°W, 29.10'
- Set Spk in 14" Elm S85°W, 26.30'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 Nov. 1, 1996 Date  Chairman



Signed by 
 Surveyor's Michigan License No. 26466

Date 12-13-96