

MAY 28 1997

OTSEGO COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO ACT 345, PA 1990

For corners in

Otsego

(County)

Located In: N. CHESTER TOWNSHIP Corner Code #

1. Public Land Survey	T <u>30N</u> R <u>2W</u>	<u>B-9</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR REC
96 DEC 30 PM 2:
EVELYN M. PRATT
CLERK / REGISTER OF C

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, James L. Schwandt, in a field survey on Oct. 21, 1996 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9		●											
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

B-9 T30N-R2W
G.L.O. Harvey Mellen, 1856
18" Y. Pine N71°W, 20 Links (13.20')
14" W. Pine S12°E, 21 Links (13.86')

CSR (2-152)
David M. Hoffman
18" Pine S80°W, 27 1/2 Links (18.15')
16" Pine N35°E, 52 Links (34.32')

CSR (3-518)
Stanley Thorson, 1968
Caldwell Notse, Set 1/2" Bar from Hoffman Wit's
10" W. Birch S15°W, 28.60'
16" Pine N35°E, 34.32'
18" Pine S80°W, 18.15'


LCRC (2-122)
Gerald R. McKelvey #19001, 1978
Fnd 1/2" Bar & Witnesses, Set O.C.M.
Spk 6" W. Birch S11°W, 58.19'
Spk 8" Maple N53°W, 52.54'
Spk 6" Aspen N62°E, 43.00'
Spk 10" W. Birch S67°E, 23.16'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Fnd O.C.M.
Fnd Spk in 8" W. Birch S11°W, 58.19'
Fnd Spk in 10" Maple N53°W, 52.54'
Fnd Spk in 10" Aspen N62°E, 43.00'
Fnd Spk in 13" W. Birch S67°E, 23.16'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

O.C.M., and is accepted as a careful & faithful reestablishment of the position of the original corner.
Fnd Spk in 8" W. Birch S11°W, 58.19'
Fnd Spk in 10" Maple N53°W, 52.54'
Fnd Spk in 10" Aspen N62°E, 43.00'
Fnd Spk in 13" W. Birch S67°E, 23.16'



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Nov. 1, 1996 [Signature]
Date Chairman

Signed by James L. Schwandt
Surveyor's Michigan License No. 26466

Date 1-1-96