

OTSEGO COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 DEC -6 PM 1:28
 W. L. H. PRATT
 CLERK / REGISTER OF DEEDS

For corners in

Otsego (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R 3W	C-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James L. Schwandt, in a field survey on Oct. 12, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

C-9 T30N-R3W
 G.L.O. Addison Brewer, 1856
 Set Post
 18" W. Pine N66°W 7 "O" (4.62')
 10" W. Pine S18°E 17 "O" (11.22')

G.F. Delamater, June 1923
 Fd. Cedar Post that was reset by Hoffman from Gov't B's

Delamater, May 1931
 Fd. Post
 Set 1/2" x 30" in corner
 Conc. Mon. S45°E 46.7'
 2 1/2" pipe N45°W 37.0'

Wynn W. Wakenhut #8897
 Fd. 1/2" Iron 1973
 Fd. 2 1/2" Pipe N45°W 37.20'
 Fd. Conc. Mon. S45°E 46.64'
 Set Spk. 9" Pine S60°W 69.96'
 Set Spk. 18" Pine S35°W 78.62'
 LCRC L.1 Pg.295

James L. Schwandt #26466
 January 20, 1987
 Fd. 1/2" bar
 Fd. 2 1/2" pipe N45°W 37.23'
 Fd. Conc. Mon. S45°W 46.63'
 Fd. Spk. 18" Pine S35°W 78.81'
 Fd. Spk. 8" Poplar S75°E 18.83'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-9 Fd. 1/2" bar over top of remains of cedar post. J.L.S. in 1987 Fd. G.F.D. 2 wit from 1931. G.F.D. Fd. Cedar post in 1923 that Hoffman reset from Gov't B's Conc. Wit Mon. Fd. By W.W.W. in 1973 date back to G.F.D. 1931.

Fd. 2 1/2" pipe N45°W 37.21'
 Fd. Blz & Tag 8" Poplar S45°E 18.48'
 Fd. Blz & Spk. 18" Pine S35°W 78.88'
 Fd. Conc. Mon. S45°E 46.68'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner.

C-9 O.C.M. set replacing 1/2" Ir. Bar
 Fd. 2 1/2" pipe N45°W 37.21'
 Fd. Blz & Tag 8" Poplar S45°E 18.48'
 Fd. Blz & Spk. 18" Pine S35°W 78.88'
 Set Blz & Tag 4" Poplar S24°E 35.35'
 Fd. Spk 5" Tri-Maple S70°E 37.25'

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Nov. 27, 1995
 Date

[Signature]
 Chairman

And is accepted as a careful and faithful perpetuation of the position of the original corner.

Signed by *James L. Schwandt*
 James L. Schwandt, PS
 Surveyor's Michigan License No. 26466

Date 11-22-95

