

Surveying

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30. NR. 4 W. . . .

----- Otsego ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 12 and 13 . . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap . . .

WITNESSES TO CORNER -----

5" Aspen - S21W - 22½ links

30" W. Pine stump - S82E - 55½ links

* 40" W. Pine stump - N13E - 86 links

* G.F. DeLaMater NBT

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey of Section 14. Found a pointed iron in place as previously established by G.F. DeLaMater in 1934. Government BTs gone but corner conforms good for midpoint and line between section corners. Corner was set to identify state land boundary. Falls in north wheel rut of E-W trail road.

Corner was placed and witnessed 10-8-59.

SURVEYORS SEAL

SIGNED *Truman J. Oetting* DATE 10/12/59
REGISTERED LAND SURVEYOR