

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30 NR 4 W

Oshtemo COUNTY

DESCRIPTION OF CORNER North $\frac{1}{8}$ corner on N-S $\frac{1}{4}$ line of Section 14

DESCRIPTION OF CORNER MONUMENT $\frac{1}{2}$ " x $\frac{3}{4}$ " pipe

WITNESSES TO CORNER

BT 30" W. Pine stump - N33E - $88\frac{1}{2}$ links

BT 30" W. Pine stump - N72W - $91\frac{1}{2}$ links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey of Section 14. Corner was established by survey procedure for the subdivision of sections, at midpoint on line between $\frac{1}{4}$ corners. This point falls exactly in line with Sanborn's survey, but is 4 links north of his $\frac{1}{8}$ post, possibly due to an erroneous measurement of this $\frac{1}{2}$ mile. Corner was set to identify state land boundary.

Corner was placed and witnessed 10/9/59.

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 10/15/59
REGISTERED LAND SURVEYOR