

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30 NR. 4 N.

Otsego COUNTY

DESCRIPTION OF CORNER 1/4 corner at center of Section 14

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

BT 6" Ironwood - S88W - 33 links

BT 36" W. Pine stub - N13W - 130 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established by Forestry Division survey crew while making a survey of Section 14. Set corner at intersection of true 1/4 lines. This point appears to be about three links NE of a possible location of the center as established by Sanborn in 1883. A large Hemlock, standing but nearly dead, in place for Sanborn's SE witness-- but could find no evidence of a post. After consideration, it was concluded that our resurvey more accurately designates the proper location for the center post, since no other monumentation prevailed.

Corner was placed and witnessed 10/9/59.

SURVEYORS SEAL

SIGNED Kenneth J. O'Leary DATE 10/15/59
REGISTERED LAND SURVEYOR