

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30. NR. 4 W. . . .

----- Otsego ----- COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 11 and 14 . .

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4# brass cap -----

WITNESSES TO CORNER -----

40" W. Pine stp - N13E - 86 links

40" W. Pine stp - N64W - 47 links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR
RESTORED.

This corner was restored by Forestry Division survey crew while making a survey of Section 14. Set corner from site of probable NE government BT. This point checks exactly for midpoint between section corners, although somewhat out of line. This appears to be the corner as identified by Sanborn in 1883 since it checks his N-S 1/4 line and the measurements as prescribed by his corners along this line.

Corner was placed and witnessed 10-9-59

SURVEYORS SEAL

SIGNED *Kenneth J. Ostling* DATE 10-12-59
REGISTERED LAND SURVEYOR