

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30 N.R. 4 W


Otsego COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 22 and 23

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/28/61

WITNESSES TO CORNER.....



7" W. Pine - 869W - 22.6 feet

5" Maple - N36W - 23.0 feet

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established while making a survey of Section 23. Set corner at midpoint between section corners, at a point calculated to introduce an 18 minute deflection at the 1/4 corner, as prescribed by the U.S. record. Falls on west shoulder of county road. Could find no previous corner.

SURVEYOR'S SEAL

SIGNED

Kenneth J. Ostling
REGISTERED LAND SURVEYOR

DATE 10/3/61