

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 30 NR. 4 W.

Otsego COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 11-12-13-14

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap

WITNESSES TO CORNER

30" W. Pine stp - S72W - 67 links

26" W. Pine stp - N36W - 47 links

Both G.F. DeLaMater NBTs in place.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found by Forestry Division survey crew while making a survey in Section 14. Found $\frac{1}{2}$ " iron bar in place in bole of large W. Pine stump which conforms to the government corner tree, previously established by G.F. DeLaMater. Appeared to conform to pattern of survey of previous subdivision of Section 14, and was considered acceptable in this survey. Corner was restored to identify state land boundary. A Square concrete monument of unknown origin is about 95 links east and 30 links south.

Corner was placed and witnessed 10-9-59.

SURVEYORS SEAL

SIGNED *Wm. J. Ostler*
REGISTERED LAND SURVEYOR

DATE 10-12-59