

MAR 17 2000

SECTION

OTSEGO COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970 ALSO Act 345. PA 1990

OTSEGO COUNTY MICHIGAN RECEIVED FOR RECORD

99 DEC 27 PM 2:56

EYLEEN H. PRATT CLERK / REGISTER OF DEEDS

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R 4 W	A-7
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Carl I. Robinson, in a field survey on April 28, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration: GLO 1/473: James H. Mullet, 1839: Set Post-Sugar 12" S 37°W 27 lks (17.8'), Sugar 12" N 67°W 26 lks (17.2'), CSR /144 Antrim Co. Surv, Date?: Found Stake & stump of witness, buried brick-14" Sugar S 31°E 23 lks (15.2'). CSR 2/208: G.F. DeLaMater, 1920: Found Bricks set Gas Pipe-8" Elm S 22°35' E 84 lks (55.4'), 8" Cherry N 63° 15' W 1.25 ch.(82.5'). LCRC 2/156: C.I. Robinson, 1979: Found 1" Iron Pipe (gas pipe) & 14" Elm Stump S 22°35' E 54.8', set Otsego County Monument-spk Cor.Fe.Post N45°E 53.51', Spk 14" Elm N 70°W 100.49', spk 20" Maple S 65°E 55.30', spk 4" Pine S 25°W 54.55'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: Found Otsego County Monument 4" deep in gravel road, Cor.Fe.Post northeast, Blazed 25" Maple southeast, and 14" Elm stump northwest.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Otsego County Monument 4" deep in gravel road accepted as careful and faithful perpetuation of the position of the original corner-spk Cor.Fe.Post N 43°E 53.51', Blazed face 25" Maple S 59°E 55.3', spk P.Pole S 36°W 90.85', spk 14" Elm stump N 70°W 100.49', 1"x4"x48" treated stake North 33.9'.



OTSEGO COUNTY REMONUMENTATION Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990. Dec 17, 1999 Date D.E. Spaw V. Chairman

Signed by Carl I. Robinson, PE & FS, Otsego County Surveyor's Michigan License No. 16390

Date December 13, 1999