

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE

LIBER 0004 PAGE 002

Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 14 PM 4:00
EVELYN M. PRATT
CLERK/REGISTER OF DEEDS

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 30 N R 4 W	B-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2							
3												
4	7	8	9	10	11							
5												
6	16	17	18	15	14							
7												
8	19	20	21	22	23							
9												
10	30	29	28	27	26							
11												
12	31	32	33	34	35							
13												

I, Carl I. Robinson, in a field survey on October 11, 19 94
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1/508: A.P. Brewer, 1856: Post- Elm 36 N 65°E 9 lks (5.9'), Elm 16 S 55°W 7 lks (4.6').
 CSR 1/50: A.W. Bates, 1890: Found Gov't B & P-Sugar 24 S 11½°E 67 lks (44.2'), Sugar 12 N 3°E 91½ lks (60.4').
 CSR 2/184: Hoffman ?, 1919: Plow Point in corner, found Bates stump NE & root cores to SE-Sugar 12 N 4°W 1.36½ ch (50.1') "nothing else to be had".
 LCR 2/222: C.I. Robinson, 1980: found Plow Point 12" below asphalt & 20" Sugar Maple stump N 4°W 89.2'-set Otsego County Monument, spk P.Pole South 33.72', spk 12" Maple N 50°W 50.39', spk 4" Cherry North 53.66', spk 10" Tw. Maple N 40°E 51.69'.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument 1" below pavement surface (adjusted with riser) and P.Pole, Maple & Tw.Maple references. Also fits G.F. DeLamater distance to east (C-3).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument in road centerline flush with pavement surface is accepted as a careful and faithful perpetuation of the position of the original corner.

- spk 14" & 20" Tw.Maple N 40°E 51.46', spk P.Pole South 33.68', spk 20" Maple N 50°W 50.32',
 spk 18" Maple N 18°W 68.08'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

12/13/94 Date DES V. Chairman

Signed by Carl I. Robinson Date November 25, 1994
 Surveyor's Michigan License No. 16390