

SURVEY & REMONUMENTATION

APR 25 1995

COMMISSION

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

LIBER 0004 PAGE 01

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 14 PM 4:00
L. PRATT
CLERK / REGISTER OF DEEDS

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 30 N R 4 W	B-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl I. Robinson, in a field survey on December 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


GLO 1/507: A.P. Brewer, 1856: Post-Sugar 7 N 32°W 7 lks (4.6'), Sugar 9 S 50°E 9lks (5.9').
CSR 1/50: A.W. Bates, 1890: Found Gov't B & P, Sugar 15 S 6°E 63½ lks (41.9'), Linn 12 N 4 W 27 lks (17.8').
CSR 3/170: G.F. DeLamater, 1942: Found one Gov't B & P, set 1"x48" Bar-Elm 10" S 2°E 26.9', Linn 12" N 86°W 67.7'.
LCR 2/222: C.I. Robinson, 1980: Set Otsego County Monument by single porportion between A-5 & C-5
spk 6" Tw. Basswood S 13°W 42.24', spk 8" Basswood S 30°E 9.57', spk 4" Maple S 60°W 14.71',
spk 12" Cherry N 40°E 27.38'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Attempted to locate DeLamater Iron or trace of his references without success. Several tree mounds were found in vicinity of Linn without success. Fence line and parallel trails north and south of line had been cleared with heavy equipment. Distance east to C-5 closely matches DeLamater (short 1.2')
Found Otsego County Monument and all 1980 references.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument in fence line east and west, and is accepted as a careful and faithful reestablishment of the position of the corner.
spk 20" Cherry N 40°E 27.38', spk 13" Basswood S 30 E 9.53', spk 12" Tw. Basswood S 13°W 42.15', spk 6" Maple S 60°W 14.67'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
Date 12/14/94 DE Saquin
V, Chairman

Signed by Carl I. Robinson Date December 9, 1994
Carl I. Robinson, PE & PS, Otsego County Surveyor
Surveyor's Michigan License No. 16390