

SURVEY & REMONUMENTATION

APR 25 1995

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 003

COMMISSION

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 94 DEC 14 PM 4:00
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 30 N R 4 W	C-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Carl I. Robinson, in a field survey on October 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1/507: A.P. Brewer, 1856: Post-Beech 10 N 9°E 34 lks
- CSN : G.F. DeLamater, 1937: Found old stake & 1 1/2" sq. iron-Concrete Monument N 45°E 48.0'
- OCRC: Kelly, Found 1 1/2" sq. iron-Monument NE 48.0', Monument SE 46.15', P.Pole SW 53.45', 12" Maple S 20°E 104.77', 4" Pine S 45°W 59.35', 1/2" stl rod SW 48', 1" Pipe NW 46.75'
- LCR 1/261: N.F. Parker, 1973: Found 1/2" sq. iron rod, face P.Pole S 52°W 53.0', face P.Pole S 29°W 78.45', face P.Pole N 41°W 49.56'
- LCR 2/81: N.F. Parker, 1977: Found 1/2" sq. bar & conc. mon. N 45°E 48.0'-spk G.Pole S 28°E 78.8', conc. mon S 46°W 47.5'
- LCR 2/124: G.R. McKelvey, 1978: Found PK, Cabin Spk, strong dip & CFD's Mon N 45°E 48'±, set Otsego County Monument Mon. N 48°E 48.05', Mon S 42°E 46.11' Mon. S 46°W 47.61', Rd. sign post N 31°W 43.16'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument, G.Pole SE, Monuments SE & SW, ~~to P.Pole SW~~ Fits roughly proportioned GLO to N, E & S and closely to DeLmater's CSR measurements to E, S & W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument at approx. pavement centerline intersection-Concrete Monument S 42°E 46.14', spk Service Pole S 28°E 78.76', Concrete Monument S 46°W 47.77', 14" Maple N 37°W 84.64', and is accepted as a careful perpetuation of the position of the original corner.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 12/13/94 Date DES Chairman



Signed by Carl I. Robinson Date November 28, 1994
 Surveyor's Michigan License No. 16390