

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**

LIBER 0004 PAGE 70

Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 NOV -2 AM 10: 12

EVELYN M. PRATT
CLERK / REGISTER OF DEEDS

For corners in

<u>OTSEGO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N R <u>4</u> W	C-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Carl I. Robinson, in a field survey on June 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO 1/507: A.P. Brewer, 1856: Old Quarter Sec. Cor.-Sugar 10" N 46°W 10 lks (6.6'), Beech 16" N 66°E 20 lks (13.2').
 CSR 1/50: A.W. Bates, 1890: Found Gov't B & P-Sugar 18" S 62°W 30 lks (19.8'), Sugar 14" N 50°E 54 lks (35.6').
 CSR 3/20: G.F. DeLaMater, 1937: "Found hole where corner had evidently been moved" 1/2"x36" Bar in corner-
 Concrete Monument East 34.0', Elm 14" N 71°W 28.8'.
 LCR 2/124: G.R. McKelvey, 1978: Found cabin spike over GFD's 1/2" Iron, Elm stump & monument; Set Otsego County
 Monument-Concrete Monument East 34.26', spk 6" R.Pine S 37°W 37.43', spk 8" R.Pine S 82°W 63.14',
 spk 8" R.Pine N 25°W 74.23'.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found R.F. Mitchell's capped (#28417) iron over broken base of McKelvey's Otsego County Monument, DeLaMater's
 Concrete Monument and all of McKelvey's R.Pine witnesses (Note: Distances interchanged between second & third).

DEC 1 1995
COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Set Otsego County Monument at surface of asphalt-Concrete Monument East 34.36', spk 6" R. Pine S 37°W 63.15',
 spk 8" R. Pine S 82°W 37.39', spk 8" R.Pine N 25°W 74.26'. This is accepted as a careful and faithful perpetuation
 of the position of the original corner.



OTSEGO COUNTY REMONUMENTATION
 Approved by the County Survey Peer
 Group, pursuant to Act 345, PA 1990.
8/3/95 Date DES Vice Chairman

Signed by Carl I. Robinson Date June 29, 1995
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390