

APR 25 1995

COMMISSION

OTSEGO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

LIBER 0004 PAGE 04

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

94 DEC 14 PM 4:01

LYLE M. PRATT  
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

OTSEGO (County)	Located In:	Corner Code -##
1. Public Land Survey	T 30 N R 4 W	C-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												


I, Carl I. Robinson, in a field survey on December 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 1/506: A.P. Brewer, 1856: Post-Sugar 6 S 67 1/2°E 19 lks (12.5'), Sugar 12 S 70°W 13 lks (8.6').  
 CSR 3/20: G.F. DeLamater, 1937: Found Gov't B & P, set 1/2" bar-Elm 5 N 58°E 21.3', Concrete Monument N 45°W 48.0'.  
 LCR 2/124: G.R. McKelvey, 1978: Found DeLamater's 1/2" bar & Concrete Monument reference, Set Otsego County Monument-  
 Concrete Monument N 45°W 47.95', spk Quad. 6"-10" Maple S 68° E 64.84', spk 8" Maple S 3°W 26.65',  
 spk 8" Maple S 85°W 53.54'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Otsego County Monument 10" deep in fence to east & west, DeLamater's concrete monument and all of McKelvey's witnesses. Distances to north, east & west fit GLO calls within acceptable limits (south not measured).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Otsego County Monument, 10" deep under fence to east & west, and is accepted as a careful and faithful perpetuation of the position of the original corner. Spk 8"-12" Quad Maple S 60°E 64.95', spk 9" Maple S 36°E 32.14', spk 11" Maple S 3°W 26.68', spk 11" Maple S 85°W 53.54', Concrete Monument N 40°W 47.95'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

12/13/94 Date DES Chairman

Signed by Carl I. Robinson  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390

Date December 9, 1994