

**SURVEY &  
REMONUMENTATION**

APR 25 1995

**COMMISSION**

OTSEGO COUNTY REMONUMENTATION III  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 005

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

94 DEC 14 PM 4:01

LYLLYN M. PRATT  
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R 4 W	D-3
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on October 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 1/508: A.P. Brewer, 1856: Post-Sugar 12 N 75°E 16 lks, Elm 6 S 64°W 53 lks. Post & stones  
 CSR 1/20: G.F. DeLamater, 1937 Found Plow Point Sugar 6" S 42°E 36.6', Sugar 12 S 44°W 52.6', Conc.Mon. North 34.0'  
 LCR 1/185: W.W. Wakenhut, 1972: Fd. Plow Point 21" deep & Mon. North-Conc. Mon. North 33.94', cap #15410 in P.Pole S 25°E 59.36', cap #15410 in ~~Post~~ Fe.Post S 5°W 41.85', spk 3-4" Multi Beech S 45°E 82.85', spk 8" Maple S 35°W 63.65'.  
 LCR 2/124: G.R. McKelvey, 1978: Found Wakenhut's capped iron & witnesses, set Otsego County Monument- Concrete Monument North 33.94', spk 3-6" Multi Beech S 45°E 82.77', Tag in P.Pole S 25°E 39.35', tag Fe. Post S 5°W 41.85', spk 8" Maple S 35°W 63.62'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Otsego County Monument, Porter's P.Pole, DeLamater's Mon., Wakenhut's Multi Beech (Maple) & Maple.  
 Fits GLO distances ± E & W and DeLater's distances well E & W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Otsego County Monument in Pavement centerline ±-Concrete Monument North 33.94', spk in 5-10" Multi Maple (called Beech in Wakenhut's & McKelvey's records) S 42°E 82.82', tag P.Pole S 25°E 33.94', spk 8" Maple S 35°W 63.62', and is accepted as a careful and faithful perpetuation of the position of the original corner.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
12/13/94 Date DES V, Chairman



Signed by Carl I. Robinson Date November 28, 1994  
 Surveyor's Michigan License No. 16390