

SURVEY & REMONUMENTATION

APR 25 1995

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

LIBER 0004 PAGE 006

COMMISSION

<u>OTSEGO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N <u>4</u> W	D-4
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 14 PM 4:01
L. V. M. PRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on December 9, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

NOTE: Not set in original Government Land Office surveys


LCR 2/125: G.R. McKelvey, 1978: Set Otsego County Monument at intersection of $\frac{1}{4}$ lines—spk 6" Maple N 14°W 19.46', spk 8" Maple N 44°E 22.55', spk 6" Maple S 64°E 19.28', spk 6" Maple S 49°W 13.99'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument in old fence line east & west and 15'± east of old fence north, also found all of McKelvey's 1978 references. Section subdivision traverse, computations and stakeout notes were reviewed to confirm procedure.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: Otsego County Monument in old fence E & W and 15'± E of fence to N. This position not established by original government surveyors. This monument is accepted as the best available evidence of the location.

Spk 9" Maple N 44°E 22.55', spk 12" Maple S 64°E 19.28', spk 8" Tw. Maple S 49°W 13.99', spk 9" Maple N 14°W 19.46'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

12/13/94 Date DES V, Chairman

Signed by Carl I. Robinson
Carl I. Robinson, PE & PS, Otsego County Surveyor
Surveyor's Michigan License No. 16390

Date December 10, 1994