

# REMONUMENTATION

APR 25 1995

## COMMISSION

For corners in

### OTSEGO COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

LIBER 0004 PAGE 007

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>30</u> N R <u>4</u> W	D-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD

94 DEC 14 PM 4:01

LYLLYN M. PRATT  
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	16	17	18	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl I. Robinson, in a field survey on December 12, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:


**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 1/506: A.P. Brewer, 1856: Post-Sugar 9, N 9½°E 13 lks (8.6'), Elm 8 S 61°W 32 lks (21.1').  
 LCR 2/125: G.R. McKelvey, 1978: GLO corner & references not found, set Otsego County Monument at MPOL S. Sec. line-spk 8" Maple N 72°W 19.33', spk 8" Maple N 53°E 6.57', spk Quad. 10" Oak clump S 28°W 12.40', spk 10" Maple S 44°E 38.64'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Otsego County Monument 2'± South of fence to east & west & all McKelvey's 1978 witnesses. Found old tree mound N 9½°E 9'± which could be GLO Sugar reference.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Otsego County Monument 2'± south of fence to east & west is accepted as a careful and faithful reestablishment of the position of the original corner.

spk 8" Maple N 53°E 6.57', spk 12" Maple S 44°E 38.64', spk 10"-15" Quad Basswood S 28°W 12.34', ½" iron rod (PI) S 75°W 47.50', spk 10" Maple N 72°W 19.30'



**OTSEGO COUNTY REMONUMENTATION**  
 Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
 Date 12/12/94 DE Sagan  
 V. Chairman

Signed by Carl I. Robinson Date December 13, 1994  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390