

OTSEGO COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 0004 PAGE 71

For corners in

<u>OTSEGO</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 30 N R 4 W	E-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

95 NOV -2 AM 10:12

EUGEN H. PRATT  
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on June 30, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

GLO 1/500: A.P. Brewer, 1856: Old Post-Sugar 8 N 38°E 81ks (5.3') "0", Beech 12 S 25°E 30 lks (19.8') "0".  
 CSR 1/32 & 33: J.W. Sanborn, 1884: Found P & B SE-Sugar 12 S 48°W 14½ lks (9.6'), Beech S 25°E 30 lks (19.8').  
 CSR 3/18: G.F. DeLamater, 1933: Found Cedar Post-Sugar 8 N 65°E 38.0', Elm 3 S 39½°E 40.8'.  
 CSR 4/244: G.F. DeLamater, 1934: Plow Point in corner- Sugar 8 N 65°E 38.0', Elm 3 S 39½°E 40.8'.  
 LCR 1/185: W.W. Wakenhut, 1972: Found Plow Point, set ½"x24" iron w/RLS cap over-Elm 15" S 40°E 40.8', Concrete Monument East 33.65', spk 12" Tw. Beech N 30°E 61.62', spk 10" Maple S 20°E 59.60', NE corner house foundation S 60°W 103.49', spk 15" Maple N 40°E 38.01'.


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Wakenhut's ½" capped iron rod, Twin Beech, Concrete Monument, & NE house foundation (Garage added); also DeLamater's Sugar.

OTSEGO COUNTY  
 SURVEYORS  
 DEEDS  
 1995  
 COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Otsego County Monument in centerline of Bituminous road north & south, and is accepted as a careful and faithful perpetuation of the position of the original corner. Spike Twin 18" Beech N 30°E 61.64', spike 18" (Sugar) Maple N 70°E 37.90', Concrete Monument S 85°E 33.60', NE corner of Garage foundation S 70°W 96.29'.



**OTSEGO COUNTY REMONUMENTATION**

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

8/3/95 Date PE Sagan Vice Chairman

Signed by Carl I. Robinson  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390

Date July 5, 1995