

**SURVEY &
SURVEY &
REMONUMENTATION**

APR 25 1995

COMMISSION
For corners in

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

LIBER 0004 PAGE 009

<u>OTSEGO</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>4 W</u>	<u>E-3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 14 PM 4:01
EVELYN M. PRATT
CLERK / REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	A
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	13	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl I. Robinson, in a field survey on October 27, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 GLO 1/499: A.P. Brewer 1856: Post-Sugar 12 N 45°W 52 lks, Sugar 8 S 23°E 10 lks.
 CSN : G.F. DeLamater 1933: Found RR iron-Sugar 12 S 56°E 73.6', Elm 14 S 54°W 63.2', SW cor. School NE 164.5'.
 CSN : G.F. DeLamater 1937: Found RR iron & other witnesses, set Concrete Monument S 45°W 48.0'.
 LCR 1/185: W.W. Wakenhut 1973: Found Boat spike, Sugar & School Witnesses-spk P.Pole N 7°E 60.95', SW corner of School NE 164.5', spk 12" Sugar S 56°E 74.6', spk 18" Beech SW 66.6', Sub. Mon. N 45°W 51.32', spk in P.Pole N 30°W 48.81'.
 LCR 2/125: G.R. McKelvey, 1978: Found Boat Spike & Wakenhut Witnesses, Set Otsego County Monument-PK 18" Sugar S 54°E 74.73', spk P.Pole N 30°W 48.85', PK T. Pole N 64°E 60.95', Sub. Mon. N 36°W 51.35'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Otsego County Monument & McKelvey's Witnesses. Fits GLO distances to N & E ±, to S & W well, fits G.F. DeLamater distances N, E, S & W very well.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Otsego County Monument-PK T. Pole N 64°E 61.03', spk 27" Maple (Sugar) S 50°E 73.84', spk 20" Maple S 55°W 75.51', Concrete (sub) Monument N 36°W 51.40', spk T. Pole N 28°W 48.85', and is accepted as a careful and faithful perpetuation of the position of the original corner.

OTSEGO COUNTY REMONUMENTATION
 Approved by the County Survey Peer
 Group, pursuant to Act 345, PA 1990.
12/13/94 Date DE Sagamu
 V. Chairman



Signed by Carl I. Robinson Date November 28, 1994
 Carl I. Robinson, PE & PS
 Surveyor's Michigan License No. 16390