

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

<u>OTSEGO</u> (County)	Located In:	Corner Code ##
1. Public Land Survey	T <u>30</u> N R <u>4</u> W	<u>E-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 010

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD

94 DEC 14 PM 4:01

LVELYN M. PRATT
 CLERK / REGISTER OF DEEDS


Register of Deeds Stamp & File Number

I, Carl I. Robinson, in a field survey on December 12, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	A
2	6		5		4		3		2				
3													
4	7		6		5		4		3		2		1
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
 GLO 1/498: A.P. Brewer, 1856: Old Post-Beech 16 S 35°W 14 lks (9.2'), Sugar 5 N 27°W 22 lks (14.5').
 CSR 4/254: G.F. DeLaMater, date?: 3/4" Pipe, Maple 7" S 78°W (no dist given)
 LCR 2/126: G.R. McKelvey, 1978: Found 3/4" Pipe in E-W fence line, set Otsego County Monument-spk 6" Maple N 60°W 62.91', spk 10" Oak N 33°W 72.57', spk P.Pole S 89°W 16.93', 1" Angle Iron S 87°E 47.17'.
 CS 496/958: C.I. Robinson, 1992: Found Otsego County Monument, Dead Maple & Oak Stump-1" Angle Iron S 87°E 47.17', 1/2" capped Iron #19001 S 81°W 31.47', 1/2" capped Iron #26266 West 33.01', spk P/Pole S 89°W 16.93'.
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 Found Otsego County Monument 1'± south of fence to east & west, Oak stump, all McKelvey's and Robinson's witnesses, which trace back to DeLaMater's undated pipe. DeLaMater did not state how he placed pipe, but was well known for his care and accuracy. Distances north, south, east & west fit GLO within acceptable tolerances.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Otsego County Monument 1'± south of fence to east & west is accepted as a careful and faithful perpetuation of the position of the original corner.
 1" angle iron S 87°E 47.17', 1/2" capped iron rod (McKelvey) S 81°W 31.47', 1/2" capped iron rod (Schwandt) West 33.01', spk P.Pole S 89° W 16.88', spk 8" Maple N 60°W 62.91', nail 12" Maple N 24°W 95.54'.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 Date 12/13/94 DE Sorenson
 V, Chairman

Signed by Carl I. Robinson
 Surveyor's Michigan License No. 16390

December 13, 1994