

OTSEGO COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 72

For corners in

<u>OTSEGO</u> <small>(County)</small>	Located In:	Corner Code $\neq$
1. Public Land Survey	T 30 N R 4 W	G-2
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 95 NOV -2 AM 10:12  
 EVELYN R. PRATT  
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on June 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

- GLO 1/494: A.P. Brewer, 1856: Old Quarter Corner-Sugar 5 N 20°E 13 lks (8.6'), Sugar 16 S 45°W 20 lks (13.2').
- CSR 1/32: J.W. Sanborn, 1884: Sugar 26 S 45°W 20 lks (13.2' Ed. GLO B), Sugar 24 N 86°E 28 lks. (18.5').
- CSR 1/51: A.W. Bates, 1890: Post set by J.W. Sanborn in survey of Sec. 4-Elm 37 N 44½°W 89½ lks (59.1'), Sugar 18 S 4½°E 46½ lks (30.7').
- CSR 3/18: G.F. DeLamater, 1934: Found Bates P ½"x36" iron in corner- Elm 14 N 11°E 135.3', Elm 12 West 106.0'.
- LCR 1/215: G.R. McKelvey, 1973: Found DeLamater's ½" iron rod 6" below road surface & Elm West-24" Elm West 106.4', Fence Post East 22.56', Steel Fence Post West 64.45'.
- LCR 2/169: C.I. Robinson, 1980: Found two 1/8"x2" Bent Leaf Springs 0.54' apart & Elm stump West, set Otsego County Monument-nail 24" Elm stump West 106.4', nail 2" Maple N 80°E 81.85', nail 8" & 12" Tw. Maple N 25°E 109.35', nail Fence Post N 20°W 72,36'.


**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Otsego County Monument 6" deep in gravel road N & S, remains of DeLamater's Elm and Robinson's Tw. Maple. This is accepted as a careful and faithful perpetuation of the position of the original corner.

OTSEGO COUNTY  
 REGISTER OF DEEDS  
 RECEIVED  
 JUN 29 1995  
 COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Otsego County Monument 6" deep in gravel road N & S-nail P.Pole N 18°E 90.86', nail 16" & 18" Tw.Maple N 28°E 109.35', PK Cedar Post N 85°W 27.72', nail 20" Maple N 80°W 153.90'.



**OTSEGO COUNTY REMONUMENTATION**

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
 8/3/95 Date                      Vice Chairman

Signed by Carl I. Robinson Date June 29, 1995  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390