

**OTSEGO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

LIBER 0004 PAGE 73

For corners in

OTSEGO <small>(County)</small>	Located in:	Corner Code #:
1. Public Land Survey	T <u>30</u> N R <u>4</u> W	G-3
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
  
95 NOV -2 AM 10:12  
  
LYLE M. PRATT  
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3							●						
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on June 28, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- GLO 1/493: A.P. Brewer, 1856: Old Post-Sugar 16 N 40°E 13 lks (8.6'), Beech 8 S 78°W 25 lks (16.5').
  - CSR 1/32: J.W. Sarborn, 1884: Sugar 16 N 40°E 13 lks (8.6' Ed. Gov't B), Beech 18 S 52°W 67 lks (44.2').
  - CSR 1/51: A.W. Bates, 1890: Found Gov. B & P-Sugar 24 N 64°E 177 3/4 lks (117.3'), Sugar 12 S 35°E 105 lks (69.3').
  - CSR 2/92: E.J. McCallummore, 1904: Birch 5 S 45°E 108 lks (71.3'), Fence Post 7 N 45°W 53 1/2 lks (35.3').
  - CSR 2/290 & 3/18: G.F. DeLamater, 1934: Found iron in corner (Ed. Origin not clear)-Sugar 8 S 21°E 86.9', Maple 12 S 69°E 129.6', Concrete Monument N 45°W 48.0' (Ed. appears to have been added later).
  - Misc.: K.R. Larsen, 1966: Found 3/8" Iron- 8" Sugar S 21°E 86.9', 12" Maple S 69°E 129.6', P.Pole SE 129.8', T. Pole NW 43.7'.
  - LCR 1/215: G.R. McKelvey, 1973: Found 1/2" iron 4' N of centerline-10" Maple S 20°E 86.95', U.Pole N 45°W 43.71', U.Pole S 30°E 44.17'. (Note: C.I. Robinson set O.C.M. 1991-5" R.Pine S 37°W 43.90', Post N 62°E 41.11').
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found broken base of Otsego County Monument, Robinson's Cedar Post and Larsen's T.Pole

1995  
DEED  
REVISION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Reset Otsego County Monument from witnesses-PK Cedar Post N 62°E 41.11', nail P.Pole S 38°E 47.96', nail 8" R.Pine spk T.Pole N 30°W 43.71'. This is accepted as the best available evidence of the position of the original corner.



**OTSEGO COUNTY REMONUMENTATION**  
Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
8/3/95 Date [Signature] Vice Chairman

Signed by [Signature] Date \_\_\_\_\_  
Carl I. Robinson, PE & PS, Otsego County Surveyor  
Surveyor's Michigan License No. 16390