

**OTSEGO COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE** LIBER 0004 PAGE 75
Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

For corners in

OTSEGO <small>(County)</small>	Located In:	Corner Code -#
1. Public Land Survey	T 30 N R 4 W	I-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD

95 NOV -2 AM 10:13

EVELYN H. PRATT
CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Carl I. Robinson, in a field survey on June 30, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law: established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- GLO 1/484: A.P. Brewer, 1856: Old Qr. Sec. Post-Beech 15" N 59°W 25 lks (16.5'), Beech 14" S 50°E 22 lks (14.5').
 - CSR 3/48: K.J. Ostling, 1961: Set DNR Mon M.P.O.L.-W.Pine 7" S 69°W 22.6', Maple 5" N 36°W 23.0'.
 - CSR 4/524: L.L. Cavanagh, 1971: Set 1/2"x18" Bar from Ostling witnesses (C.I. Robinson set O.C.M. August 1985).
 - LCR 3/44: B.M. Jones, 1988: Fd. 1/2" Iron Bar-12" Poplar N 80°E 79.70', 6" W.Pine S 45°E 103.97'

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found Otsego County Monument 8'± west of edge of bituminous pavement; all of Ostling's witness's and all of Jones witness's (Jones was in error about 1/2" Iron Bar).

DEC 1 1995
OTSEGO COUNTY

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Otsego County Monument accepted as a careful and faithful reestablishment of the position of the original corner. Spike 12" Aspen N 80°E 80.03', spike 8" R.Pine S 45°E 104.04', spike 10" W.Pine S 75°W 22.72', spike 7" Twin Maple N 40°W 23.23'.



OTSEGO COUNTY REMONUMENTATION
Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
8/3/95 DE Sagan
Date Vice Chairman

Signed by Carl I. Robinson Date July 5, 1995
Carl I. Robinson, PE & PS, Otsego County Surveyor
Surveyor's Michigan License No. 16390