

OTSEGO COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970  
ALSO Act 345, PA 1990

OTSEGO COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
95 NOV -2 AM 10:13  
L. V. H. M. PRATT  
CLERK / REGISTER OF DEEDS

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 30 N R 4 W	I-10
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Carl I. Robinson, in a field survey on July 26, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- GLO 1/483: A.P. Brewer, 1856: Old Qtr Sec Cor-Sugar 14" N 40°W 32 lks (21.1'), Sugar 14" N 63°E 26 lks (17.2').
- CSR 3/52: G.F. DeLaMater, 1934: 1"x30" bar in cor, Found P. & roots of one B-Sugar 16" N 22°E 51.9', Sugar 24" N 89°W 24.9'.
- CSR 3/440: S.O. Thorsen, 1958: Found 1/2" bar- Elm 10" N39°E 68.4', Double Elm 18" N 79°W 56.8'.
- OCRC Notes: Kelly, undated: spike Elm 16" N.E. 38.5', spike Sugar 24" Stump W. 25.5'.
- LCR 1/313: W.W. Wakenhut, 1973: Found 1/2" bar & 10" Elm N 39°E 68.4'-Stl. Fe.Post N 60°E 26.8', spike P.Pole S 50°W 48.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2"x18" Iron Rod at pavement surface over 30" axle shaft (removed); Thorsen's & Kelly's Elms (3ea. all dead); and Wakenhut's Steel Fence Post & P.Pole.

DEC 1 1995  
SUBMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Otsego County Monument over 1/2"x18" Iron Rod at corner accepted as a careful and faithful perpetuation of the position of the original corner-ctr. 4" dia. Steel Fence Post N 70°E 27.05', spk P.Pole S 54°W 48.80', ctr 3" dia. Steel Fence Post N 79°W 50.94', spk P.Pole N 20°W 75.85'.



OTSEGO COUNTY REMONUMENTATION  
Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
8/3/95 Date  
DES Vice Chairman

Signed by Carl I. Robinson Date July 27, 1995  
Surveyor's Michigan License No. 16390