

OTSEGO COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**

LIBER 0004 PAGE 78

Filing Requirement of Act 74, Mich. P.A. 1970  
 ALSO Act 345, PA 1990

For corners in

OTSEGO (County)	Located in:	Corner Code #
1. Public Land Survey	T 30 N R 4 W	I-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 95 NOV -2 AM 10:13  
 EVELYN M. PRATT  
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							

I, Carl I. Robinson, in a field survey on July 25, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 1/483: A.P. Brewer, 1856: Old Post Corner-Hemlock 12" N 30°E 7 lks (4.6'), Hemlock 10" N 84°W 16 lks (10.6').  
 CSR 3/52: G.F. DeLaMater, 1934: Found 3 old P's, 1/2"x30" bar in corner-Maple 8" N 11 1/2°E 140.0', W.Pine 14" S 30°W 24.2  
 OCRC Notes: Kelly, undated: P.Pole S 52°W 56.7' & GFD's two 1934 witnesses.  
 Misc. Rec: L.Cavanagh, 1971±: Found 1/2" bar & GFD's two 1934 witnesses.  
 LCR 1/313: W.W. Wakenhut, 1973: Found 1/2" bar-Cor. Fe. Post North 33.5', Steel Fe. Post in Concrete N 35°E 37.2', spike 14" Forked Cherry S 55°E 32.7', spike 30" W.Pine S 30°W 24.25'.  
 LCR 2/147: D.E. Sagasser, 1979: Found 1/2" bar & all of Wakenhut's witnesses, Raised corner with 3/4" Pipe placed Monument Box-Fe. Cor. Post North 33.69', Bent Steel Fe. Post N 35°E 37.4', 9" W.Pine S 38°E 28.98', 30" W.Pine S 30°W 24.13'.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found 3/4" Capped Iron Pipe in Monument Box, DeLaMater's Maple & W.Pine; and Sagasser's W.Pine.

REC. 1995  
 COMMISSION

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 3/4" Capped Iron Pipe over 1/2" Iron Rod in Monument Box at the corner is accepted as a careful and faithful perpetuation of the position of the original corner-spk 22" Maple N 20°E 140.45', tag 12" W.Pine S 33°E 28.98', spk 30" W.Pine S 38°E 24.25', spk P.Pole N 40°W 58.35'.



OTSEGO COUNTY REMONUMENTATION  
 Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.  
 8/3/95 Donald E. Sawyer  
 Date Vice Chairman

Signed by Carl I. Robinson  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390

Date July 27, 1995