

OTSEGO COUNTY REMONUMENTATION
 LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 DEC -6 PM 1:28
 EVELYN H. PRATT
 CLERK / REGISTER OF DEEDS

For corners in

Otsego (County)	Located in:	Corner Code #
1. Public Land Survey	T30N R4W	M-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, James L. Schwandt, in a field survey on Oct. 13, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 M-4 T30N-R4W

G.L.O. Addison P. Brewer, 1856
 Set Post
 12" Birch S32°W 4 (2.64')
 18" Hemlock N16°W 17 (11.22')

Gerald R. McKelvey #19001
 June 10, 1975
 Fd. 3/4" iron pipe & old blazes
 Origin unknown ± 5' South of E-W fence
 Tag #19001 in 4" Aspen S52°E 63.45'
 Tag #19001 in Blazed 10" Elm S16°E 42.02'
 Tag #19001 in 4" Aspen N55°E 70.83'

Carl I. Robinson Set
 O.C.M. from G.R.M. wit.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

M-4 Fd. O.C.M. set by C.I.R. from G.R.M. wit. G.R.M. Fd. 3/4" pipe & old blazes - Origin unknown. No tie to G.L.O. No wit Fd.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-4 Fd. O.C.M.

Cor. Fence Post Airport N87°E, 73.79'
 Set Tag & Blz 6" Aspen S54°E 59.13'
 Set Tag & Blz 4" Aspen S29°E
 Set Tag & Blz 5" Cherry S85°W 85.22'

And is accepted as a careful and faithful reestablishment of the position of the original corner.

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer
 Group, pursuant to Act 345, PA 1990

Nov. 27, 1995
 Date

[Signature]
 Chairman

Date 11-22-95

Signed by James L. Schwandt
 James L. Schwandt, PS
 Surveyor's Michigan License No. _____

26466

