

OTSEGO COUNTY REMONUMENTATION  
 LAND CORNER RECORDATION CERTIFICATE  
 Filing Requirement of Act 74, Mich. P.A. 1970

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD  
 95 DEC 27 AM 9:38  
 EVELYN H. PRATT  
 CLERK / REGISTER OF DEEDS

For corners in

| Located In:   | Corner Code # |
|---|---------------|
| 1. Public Land Survey<br>T <u>30</u> N R <u>4</u> W           | <u>M-7</u>    |
| T _____ R _____   | _____         |
| T _____ R _____   | _____         |
| T _____ R _____   | _____         |
| 2. Property Controlling in Section<br>S _____ T _____ R _____ | _____         |
| S _____ T _____ R _____                                       | _____         |
| 3. Miscellaneous Property in Sec.<br>S _____ T _____ R _____  | _____         |
| S _____ T _____ R _____                                       | _____         |

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, James L. Schwandt, in a field survey on November 14, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

|    | A  | B | C  | D | E  | F | G  | H | I  | J | K  | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 1  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 2  | 6  |   | 5  |   | 4  |   | 3  |   | 2  |   | 1  |   |   |
| 3  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 4  | 7  |   | 8  |   | 9  |   | 10 |   | 11 |   | 12 |   |   |
| 5  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 6  | 18 |   | 17 |   | 16 |   | 15 |   | 14 |   | 13 |   |   |
| 7  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 8  | 19 |   | 20 |   | 21 |   | 22 |   | 23 |   | 24 |   |   |
| 9  |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 10 | 30 |   | 29 |   | 28 |   | 27 |   | 26 |   | 25 |   |   |
| 11 |    |   |    |   |    |   |    |   |    |   |    |   |   |
| 12 | 31 |   | 32 |   | 33 |   | 34 |   | 35 |   | 36 |   |   |
| 13 |    |   |    |   |    |   |    |   |    |   |    |   |   |

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 M-7 T30N-R4W

|  |  |  |  |
|--|--|--|--|
| G.L.O. Addison P. Brewer,<br>1856<br>Set Post<br>12" Beech N79°W 11 (7.26')<br>12" Beech S54°W 23 (15.18') | S. Thorsen, 1956<br>Book 3, Page 324, O.C.R.<br>1/2" x 18"<br>12" B. Cherry S15°E 93.40'<br>12" B. Cherry S72°W 208.8' | James L. Schwandt<br>#26466<br>December 21, 1982<br>Fd. 1/2" pipe<br>P.P. N73°E 87.13'<br>8" R. Pine N05°E<br>42.46'<br>10" Multi. J. Pine<br>S17°E 41.46' | Carl I. Robinson<br>Set O.C.M. at<br>witnessed location. |
|--|--|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

M-7 Fd. O.C.M. set by C.I.R. at witnessed location. J.L.S. fd. 1/2" pipe of unknown origin in 1982, but could not trace it to S.O.V. cor. or to G.L.O.

Fd. nail w/yellow cap N5°E 42.50' (42.46R)  
 Fd. J.L.S. tag 8" R. Pine N10°E 38.36'  
 Fd. nail in p.p. N73°E 87.33' (87.13R)  
 Fd. nail w/yellow cap 10" Multi J. Pine S17°E 41.50' (41.46R)  
 Fd. spk. 8" R. Pine N50°W 62.80' (63.00R)

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

M-7 Fd. O.C.M.

Fd. nail w/yellow cap N5°E 42.50' (42.46R)  
 Fd. J.L.S. tag 8" R. Pine N10°E 38.36'  
 Fd. nail in p.p. N73°E 87.33' (87.13R)  
 Fd. nail w/yellow cap 10" Multi J. Pine S17°E 41.50' (41.46R)  
 Fd. spk. 8" R. Pine N50°W 62.80' (63.00R)

OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

Dec 15, 1995 Date [Signature] Chairman

And is accepted as a careful and faithful reestablishment of the position of the original corner.

Signed by James L. Schwandt  
 Surveyor's Michigan License No. \_\_\_\_\_

Date 12-21-95

