

# LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. PA 1970

For Corners In: Otsego (County)	Located In	Corner Code #
1. Public Land Survey	T <u>30N</u> R <u>4W</u>	<u>J-9</u>
2. Property Controlling in Section	T _____ R _____	_____
	S <u>23</u> T <u>30N</u> R <u>4W</u>	<u>15</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No: \_\_\_\_\_ Recorded Plat: \_\_\_\_\_

5. Private Claims: \_\_\_\_\_

I, Carl T. Kiiskila, in a field survey on April 20, 1998 do hereby state that under requirements of PA 74, Michigan PA of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9									●				
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

J-9 G.L.O. Harvey Mellen D.S., July 1857  
Set quarter section post  
Wit: 12" Hemlock N28°E 13 links  
9" Beech S49°N 8 links

15- Kenneth J. Ostling RLS# 10068 established this corner while doing a survey for the Department of Conservation in 1961.

G.F. DeLamater set a 1/2" iron bar from witnesses furnished by Co. Surveyor Thorsen, no date.

Kenneth J. Ostling, October 3, 1961, found 1/2" iron bar replaced with standard DNR monument.

Wit: 16" W. Pine N78°E 85.7'  
6" W. Pine N11°E 42.3'  
12" W. Pine S46°W 68.8'

B. Description of corner evidence found and/or method applies in restoring or re-establishing corner:

J-9 Found a standard DNR monument as set by Kenneth J. Ostling.

15- Re-established the Southeast corner of the Southwest quarter or the Southwest quarter section 23 per standard BLM instructions for subdivision of a section.

Kenneth J. Ostling's corner was lost.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-9 Standard DNR monument  
Wit: 4" White pine N02°E 34.49'  
4" White pine S87°W 7.97'  
7" Maple S10°E 34.06'  
20" White pine N87°E 85.70'

15 Set 5/8" X 32" re-rod with PS cap #33981  
Wit: 36" Pine stump N09°E 21.56'  
10" Maple N76°E 20.06'  
5" White pine S17°W 37.90'  
7-4" twin Maple S57°W 15.19'  
32" White pine N83°E 87.18'

Signed by: Carl T. Kiiskila  
Surveyor's Michigan License No.: 33981

Date: 1-20-00

