

LAND CORNER RECORDATION CERTIFICATE LIBER 0004 PAGE 87
 Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Otsego (County)	Located In:	Corner Code #
1. Public Land Survey	T 30N R 1W	I-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Section	S T R	
	S T R	

OTSEGO COUNTY
 MICHIGAN
 RECEIVED FOR RECORD
 95 NOV -3 PM 1:37
 EVELYN M. PRATT
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, James L. Schwandt, in a field survey on August 29, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
 I-9 T30N-R1W

- | | | |
|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------|
| G.L.O. Harvey Mellen, 1857
Set Post
12" Sugar N48°E 23 (15.18')
20" Hemlock S13°W 16 (10.56') | A.W. Bates, 1890
Sugar 10" N43°E 94 1/2 Lks. (62.37')
Hemlock 20" S2°E 45 Lks. (29.70') | Stanley Thorson, 1962
MSHD - Notes (doesn't state what was fd.)
T.P. N67°W 85.17'
T.P. N70°E 56.45'
P.P. S15°E 63.65' |
| Wynn W. Wakenhut #8897, 1972
Fd. 1/2" iron 2' South of N. edge of pavement.
Cross in South end of large flat boulder N14°W 132.20'
Torque tube S16°E 105.24'
MSHD tag T.P. N70°W 85.26'
Spk. T.P. N50°E 54.69'
Spk. P.P. S20°E. 67.50' | G.F.D., 1933
Fd. both Gov't B's, no P.
1/2" bar in corner
Conc. mon., N37 1/2°E 55.6'
Large stone, N14°W 132.6'
Torque tube, S16 1/2°E 105.7' | Larry M. Gerschbacher, 1976
Fd. 1/2" iron bar
T.P. N71°E 54.30'
T.P. MSHD tag N69°W 85.32'
P.P. S18°E 61.55' |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 LMG Fd WWW MSHD Tag in T.P. JLS Fd. WWW Wit in P.P.


- I-9 Fd. 1/2" bar and adjacent 1" bar in Mon. Box
 1. Fd. Spk. in P. Pole S25°E 67.56'
 2. Fd. Spk. in P. Pole S30°W 122.70'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-9 Otsego County Mon. Set in Mon. Box replacing 1/2" iron bar.
 1. Fd. Spk. in P. Pole S25°E 67.56'
 2. Fd. Spk. in P. Pole S30°W 122.70'
 3. Edge of pavement North 5.5'
 4. Set Spk. in Fence corner post N45°W 46.35'

And is a careful and faithful perpetuation of the position of the original corner.

OTSEGO COUNTY REMONUMENTATION
 Approved by the County Survey Peer Group, pursuant to Act 346, PA 1990.
 Nov. 2, 1995
 Date _____ Chairman _____



Signed by James L. Schwandt
 James L. Schwandt, PS
 Surveyor's Michigan License No. 26466

Date 11-2-95