

REMONUMENTATION

APR 25 1995

COMMISSION

For corners in

OTSEGO COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970
ALSO Act 345, PA 1990

LIBER 0004 PAGE 046

OTSEGO COUNTY
MICHIGAN
RECEIVED FOR RECORD
94 DEC 29 PM 1:31
EVELYN M. PRATT
CLERK / REGISTER OF DEEDS

_____ Otsego _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 1 W	A-5
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Carl I. Robinson, in a field survey on April 18, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


- GLO 2/10: J. Mullet, 1840: set Post Sugar 16" S 52°W 15 lks (9.9'), Sugar 8" N 28°E 12 lks (7.9').
 CSR 1/107: D.M. Hoffman, 1907: Sugar 16" S 52°W 15 lks (9.9'), Sugar 14" N 20°E 46 lks (30.4'), Sugar 12" S 45°E 42 lks (27.7')- (Ed. First Sugar was GLO, therefore I assumed he found GLO Post).
 CSR 3/124: G.F. DeLaMater, 1938 1/2" x 36" bar in corner established on twp. line between corners of which we were sure (A-4 & A-7)-Large Stone N 89°E 51.8', Concrete Monument S 37°W 50.2', Triple W. Birch 4" S 88°W 5.9'.
 G.F. DeLaMater, 1940: Found 100' error in 1938 work and adjusted corner to new position.
 LCRC 2/143: G.R. McKelvey, 1979: Found 1/2" Iron Rod, W. Birch & Concrete Monument witnesses, set Otsego County Monument-1/2" Iron Rod S 08°E 74.61', spk 9" Aspen N 37°E 41.09', spk 12" W. Birch S 88°W 5.66', Concrete Monument S 37°W 50.12'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Otsego County Monument and all of McKelvey's witnesses which include DeLaMater's Concrete Monument & triple W. Birch. DeLaMater proportioned this corner between A-4 & A-7, I find it fits this proportion within one foot.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Otsego County Monument-spik 11" Aspen N 37°E 41.09', 1/2" Iron Rod S 08°E 74.61', Concrete Monument S 37°W 50.12', spk 12" Tri W. Birch S 88°W 5.66'. This corner is accepted as a careful and faithful reestablishment of the position of the original corner.



OTSEGO COUNTY REMONUMENTATION

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.
 12/22/94 Date DE Samson V. Chairman

Signed by Carl I. Robinson
 Carl I. Robinson, PE & PS, Otsego County Surveyor
 Surveyor's Michigan License No. 16390

Date December 15, 1994