

OTSEGO COUNTY REMONUMENTATION  
**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 ALSO Act 345, PA 1990

LIBER 0004 PAGE 79

For corners in

OTSEGO (County)	Located In:	Corner Code #
1. Public Land Survey	T 31 N R 1 W	A-8
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

OTSEGO COUNTY  
 MICHIGAN  
 RECEIVED FOR RECORD

95 NOV -2 AM 10:13

EVELYN H. PRATT  
 CLERK / REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Carl I. Robinson, in a field survey on July 10, 19 95  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 GLO 2/9: John Mullet, 1840: Set Post-Hemlock 12" S 73°E 12 lks (7.9'), Beech 10" N 33°W 32 lks (21.1').  
 CSR 1/108: D.M. Hoffman, 1907: Post-Hemlock 12" S 73°E 13 lks (8.6'), Hemlock 12" S 24°E 29 lks (19.1').  
 CSR 2/444: G.F. DeLaMater, 1931: W.Pine stump 36" N 62°E 12.0', Hemlock 12 (found old stump badly rotted) S 73°E 8.6', W.Pine stump 48" S 5°E 54.3'; 1933: 1/2"x36" bar in corner-Concrete Monument West 34.0'.  
 CSR 3/282: S.O. Thorsen, 1953: Placed 1/2"x48" Bar-Maple 7" S 40°W 65.5', Concrete Monument West 34.0'.  
 LCR 1/457: P.E. Chenard, 1975: Found 1/2" Bar-DeLaMater's Monument, Thorsen's Maple & fence West-P.Pole N 20°E 75.25', 12" Maple S 40°W 65.68', Concrete Monument West 34.0', Quad Maple N 85°W 41.18'.  
 LCR 2/144: G.R. McKelvey, 1979: Found 1/2" Iron Rod & P.Pole NE (All other references destroyed by Gas Line clearing, set Otsego County Monument-P.Pole N 20°E 75.25', spike Fe.Post S 67°E 31.79', spike 10" Aspen N 84°W 107.84', 4" Maple N 11°W 75.26'.  
 B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 Found Otsego County Monument (4" dia. extendable), Chenard's P.Pole & McKelvey's Aspen.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
 Otsego County Monument in corner is accepted as a careful and faithful perpetuation of the position of the original corner-nail P.Pole N 25°E 75.15', nail 9" Maple N 81°E 60.00', nail 8" Maple S 68°W 113.08', spike 16" Aspen N 76°W 107.78'.



**OTSEGO COUNTY REMONUMENTATION**

Approved by the County Survey Peer Group, pursuant to Act 345, PA 1990.

8/3/95 Date David E. Sagan Vice Chairman

Signed by Carl I. Robinson Date July 18, 1995  
 Carl I. Robinson, PE & PS, Otsego County Surveyor  
 Surveyor's Michigan License No. 16390